

(For uploading on Institute website and CPP portal)

लिमिटेड टेण्डर नं.-1/2023 (वर्क्स)

विषय: Construction of Water Storage Tank (5.5 m x 3.0 m x 2.3 m) at experimental farm, Samni of ICAR-CSSRI, RRS, Bharuch

महोदय,

उपरोक्त कार्य को करने के लिए सीलबंद टेण्डर आमन्त्रित किये जाते हैं। कार्य का ब्योरा, नियम व शर्तें संलग्न हैं। टेण्डर का लिफाफा सीलबंद होना चाहिये। यदि सीलबंद नहीं हुआ तो वह स्वीकार नहीं किया जायेगा तथा निरस्त किया जा सकता है। टेण्डर के लिफाफे पर कार्य का नाम व अन्तिम तिथि आवश्यक रूप से लिखी होनी चाहिये अन्यथा टेण्डर मान्य नहीं होगा। टेण्डर प्राप्त करने की अन्तिम तिथि 13-06-2023 समय 11.00 बजे पूर्वाह्न है व दिनांक 13-06-2023 को 2.30 बजे तक टेण्डर बाक्स में टेण्डर डाला जा सकता है एवं 13-06-2023 को ही फर्म के मनोनीत की उपस्थिति में 3.00 बजे अपराह्न में टेण्डर खोले जायेंगे। इच्छुक फर्म अपने सीलबंद टेण्डर को पूर्ण विवरण एवं संलग्न दस्तावेजों आदि के साथ अध्यक्ष, केन्द्रीय मृदा लवणता अनुसंधान संस्थान, क्षेत्रीय अनुसंधान केन्द्र, भरुच के नाम पर रजिस्टर्ड/स्पीड पोस्ट/डाक/कोरियर द्वारा भेजें या व्यक्तिगत तौर पर आकर टेण्डर बॉक्स में डालें जो कि संस्थान के सुरक्षा अनुभाग में रखा गया है। देय तिथि व देय समय के पश्चात प्राप्त कोई भी टेण्डर किसी भी रूप में स्वीकार नहीं होगा। यह सूचना संस्थान की वेबसाइट www.cssri.res.in तथा CPP Portal पर उपलब्ध है।


22/5/23
अध्यक्ष

TENDER FORM NO. 1/2023 (WORKS)

On behalf of Secretary, ICAR, Director, ICAR-CSSRI, Karnal invites sealed tenders from reputed contractors for the under mentioned work for ICAR-CSSRI, RRS, Experimental farm, Samni (Bharuch).

S. N.	Description of Items/ Name of work	Place of Work	EMD Amount
1.	Construction of Water Storage Tank (5.5 m x 3.0 m x 2.3 m)	ICAR-CSSRI, RRS, Experimental farm, Samni (Bharuch)	4000/-

TERMS & CONDITIONS:

1. The envelope containing tender and other documents should be clearly written the name of the work, Tender no., closing date failing which the tender will be returned without opening.
2. The contractor should mention the correct postal address and contact no. The contractor should inform to the office in writing immediately about any change in address. Institute shall not be responsible for non – receipt of document due to postal delay/ undelivered/ non- recipient at your end.
3. The item wise rate may be quoted on the printed letter pad of the firm after inspection of site (If required) and clarification in respect of the detail of the tender document can be sought from CSSRI, RRS, Bharuch.
4. Work shall be carried out as per the instruction, direction and satisfaction of the Head of the Station.
5. The rate should include all labour and materials charges, transportation, tool and tackles etc. as required for completing the work.
6. The work should be started within 10 days from the date of issue of work order failing which the performance security will be forfeited on the recommendation of the Head of the Station.
7. The work should be completed within 3 months from the date of issue of work order failing which performance security will be forfeited. Extension of time may be granted to the contractor beyond the agreed time of completion of the work taking into account the delay due to unavoidable circumstances. Proposal for extension should be given at least two weeks before the expiry period for the approval of the Competent Authority.
8. In case the contractor fails to complete the work within the stipulated/extended period of time, penalty shall be imposed on the contractors @ 0.25% per week, maximum of 2.5% of the total cost of the work.
9. The Director shall have the liberty to postpone or not to execute any item of work and the contractor shall not be entitled to any compensation for non execution of such items of work.
10. All the material purchased for the said work by the contractor shall be as per the CPWD/ISI/BIS standards/specification and got approved by the Head of the Station. The inferior quality or rejected material is to be removed immediately from the site failing which the same will get removed by the Institute and expenses involved will be deducted from the contractor's bill.
11. The contractor should submit the detail of the measurement in A4 size paper (typed) standard format for the items of work executed under the agreement after completion of work duly signed and verification of the Head of the Station.
12. The water/Electricity as required for the work & curing at site (if not available) shall be arranged by the contractor for which no extra payment shall be made.
13. The store will not be provided to contractor for storing of the construction material & their tools.
14. In case of dis-satisfactory work the contract may be terminated at any time and in such case the performance security deposited shall be forfeited.

15. In case the contractor fail to work within the stipulated/extended period of time and according to our satisfaction, the Director, ICAR-CSSRI shall have right to terminate the contract and get the work through any Other firm or agency. In such case, the performance security of the contractor shall be forfeited.
16. Quantity of work may be increased or decreased according to the actual need of work and hence, minor deviation of work shall be undertaken as per quoted rate without asking any compensation.
17. The contractor has to deposit Security Deposit @ 5% of the total estimated cost through D.D./ Bank Guarantee for the period of contract towards proper performance of the contract within 15 days of issue communication letter for acceptance of rates by the Institute which shall be released after one year of successful completion of completed works.
18. The contractor has to pay minimum wage as per the rate of government instructions time to time to their labours force engaged for the civil work.
19. All other liabilities including taxes such as Income Tax, GST and other taxes, labour cess, sale tax/Vat, service tax, ESI/EPF etc. imposed by the government from time to time shall be deducted from the bill of contractor.
20. The tenderer should quote total amount after adding all the sub head in case total amount is not given in the quotation the tender shall be treated as in-complete and to be rejected.
21. After completion of the work, the left over material at the site, if any, shall be removed and site should be cleaned within 10 days.
22. The Director, CSSRI, Karnal reserves the right to accept or reject any or all the quotation/ tenders without assigning any reason there of and the decision of the Director, CSSRI, shall be final and binding to all concerned parties.
23. The Director, CSSRI, Karnal also reserve the right to cancel the work, after award of work due to any administrative/ technical reason.
24. The Director, CSSRI, Karnal shall be the sole arbitrator for all disputes between contractor and the Institute. The decision of Director shall be final and binding to both the parties.
25. Any type of official implements and help will not be provided by the office.
26. All precautionary safety measure have to be followed and risk if any, is to be borne by the contractor. Office will not be responsible for any mishappening, if caused, during the execution of work to the contractor or his worker.
27. The Demand draft /banker performance security of EMD should be prepared for the work in favour of DDO, CSSRI, RRS, Bharuch.
- 28. PAN, GST, Registration of firm/Contractor must be written on the quotation/tender otherwise it would be cancelled.**
- 29. The valid photo copy of all documents including license for contractorship must also be attached.**

The above terms and conditions are acceptable to me.

Signature

Full address

Date:

Sub.: Quotation for construction of Water Storage Tank (5.5 m x 3.0 m x 2.3 m) at experimental farm, Samni of ICAR-CSSRI, RRS, Bharuch

DSR'21 Item No	Description of Item	Qty.	Unit	Rate	Amount (Rs.)
2.6.1	Earth work in excavation over areas (exceeding 30cm in depth. 1.5m in width as well as 10 sqm on plan) including disposal of excavated earth, lead upto 50m and lift upto 1.5m; disposed earth to be levelled and neatly dressed-all kinds of soils.	57.20	cum		
2.25	Filling available excavated earth (excluding rock) in trenches, plinth, sides of foundations etc. in layers not exceeding 20cm in depth: consolidating each deposited layer by ramming and watering, lead up to 50 m and lift upto 1.5 m	19.95	cum		
2.26.1	Extra for every additional lift of 1.50 m or part thereof in - All kinds of soil.	18.20	cum		
2.27	Supplying and filling in plinth with sand under floors, including watering, ramming, consolidating and dressing complete.	2.60	cum		
2.32	Clearing grass and removal of the rubbish upto a distance of 50 m outside the periphery of the area cleared.	37.50	sqm		
4.1.3	Providing and laying in position cement concrete of specified grade excluding the cost of centring and shuttering-all work upto plinth level 1:2:4 (1Cement: 2 coarse sand:4 graded stone aggregate 20 mm nominal size)	2.60	cum		
5.1.2	Providing and laying in position specified grade of reinforced cement concrete excluding the cost of centring, shuttering, finishing and reinforcement - All work upto plinth level- 1:1.5:3 (1 Cement : 1.5 coarse sand : 3 graded stone aggregate 20 mm nominal size)	14.59	cum		
5.9.2	Centring and shuttering including strutting, propping etc. and removal of form for: Walls (any thickness) including attached pilasters, butteresses, plinth and string courses etc.	92.00	sqm		
5.9.3	Suspended floors, roofs, landings, balconies and access platform.	16.50	sqm		
5.9.5	Lintels, beams, plinth beams, girders, bressumers and cantilevers.	2.75	sqm		
5.22.6	Reinforcement for R.C.C. work including straightening, cutting, bending, placing in position and binding all complete Thermo-Mechanically Treated bars.	1432	kg		
13.1.1	12 mm cement plaster of mix 1:4 (1 cement: 4 fine sand) Inside	88.65	sqm		
13.3.1	20 mm cement plaster of mix : 1:4 (1 cement: 4 fine sand) Outside	25.85	sqm		
13.18	Neat cement punning.	114.50	sqm		
19.19.1.1	Providing and fixing in position pre-cast R.C.C. manhole cover and frame of required shape and approved quality L D- 2.5 Rectangular shape 600x450 mm internal dimensions	4	each		
10.25.2	Steel work welded in built up sections/ framed work, including cutting, hoisting, fixing in position and applying a priming coat of approved steel primer using structural steel etc. as required. In gratings, frames, gates and similar worksguard bar, ladder, railings, brackets,	40	kg		
	Total				

ADDITIONAL TERMS & CONDITIONS:

The above rates should include cleaning of surface/site after completion of work.

Rates quoted are inclusive of GST and valid for one month.

Payment will be made on actual measurement basis after satisfactorily completion of work.

The work should be completed within three months from the date of issue of work order.

The contractor has to deposit Security Deposit @ 5% which shall be released after one year of successful completion of completed works.

TDS as per rules will be deducted from the bill.

Signature

Name of contractor

Full address.....

Mobile No.

Bank Name.....

Branch

IFS Code

Bank A/c No

PAN

GST No.

Registration No.